

> Pipework...

All pipe work will be in copper tubing with capillary or compression fittings as appropriate. The pipe work will be concealed wherever possible and all visible pipes will be fitted neatly and as inconspicuously as practicable. Proper provision will be made for the effects of expansion and contraction. All new pipe work containing water in unheated spaces i.e. garages or lofts will be lagged as necessary.

Where any supply pipework is to run beneath floors we will require access to the respective rooms to raise carpets and flooring as appropriate as discussed during the survey. We would appreciate you undertaking the moving of any furniture or items to facilitate access to these areas wherever possible prior to work commencing.

Gasway will relay carpets as best as practicable but will not accept responsibility for their integrity. Any re-stretching required will need to be undertaken by your own contractor.

It will be necessary to provide pressure relief and condensate pipes from new condensing boilers to a suitable point as discussed during the survey. Every effort will be made to make these as inconspicuous as possible however we will ensure current Gas Safety and Building Regulations are met accordingly.

> System Flush...

System to benefit from a full POWERFLUSH chemical treatment prior to connecting the new boiler.

Upon completion the boiler and system will be hot flushed clean using a commissioning fluid, thoroughly tested and commissioned to the boiler manufacturer's instructions. Finally a chemical inhibitor will be added for future system protection.

> Building Work...

This quotation includes providing all holes etc. required for pipe runs and making good all work disturbed afterwards but not painting and decorating, carpentry, brickwork, plastering or electrical work other than that specified. The quotation includes the removal of all scrap and waste materials from site.

N.B. Any asbestos related materials encountered on site which have not been specifically itemised will not be removed unless requested, for which an additional charge may be made.

> System Integrity

We are unable to guarantee the integrity of your existing system (especially pipework sited within concrete floors), this quotation is to replace the boiler, system controls and make good only.

> Service Interruption

Every effort will be made to restore facilities at the very earliest opportunity. However the heating and hot water system could remain out of action for the majority of the time whilst the work is in progress. Cold water supply interruption is anticipated to be minimal.

> Electrical Work...

All the necessary electrical work associated with the installation is included in this quotation. Upgrading the Main Equipotential Earth Bonding IS NOT included in this quote. Our electrician will check this during the installation and you will be advised if this does not meet current regulations and if any additional work is recommended.

New independent immersion heater or shower supplies are not included unless specifically specified.

Gasway is committed to protecting the environment. All scrap and waste materials will become the property of Gasway and will be removed and recycled as part of this agreement. The value of which together with additional monetary support from our manufacturing partners has been used to produce the price supporting element offered as part of this quotation.

> BUILDING REGULATIONS PART L

Gasway Installations undertake to meet the Building Regulation on Part L requirements however it accepts no liability in respect of any claims made where the customer has insisted on declining to follow advice given during the survey.

> WATER PRESSURE

Gasway will not accept responsibility for any failure resulting from poor or inadequate mains water pressure/volume. This is the responsibility of the Water Authority and Householder to provide a solution in the result of a problem.

Price valid for period of 30 Days from the date of this quotation. Gasway will reserve the right to realign thereafter.

=